


Top View



Side View



End View




1. Meter Yoke


A.Y. McDonald 21-207WXQQ 33 Ford VB72-7W-44-33-Q

- 2. Corporation Stop A.Y. McDonald 4704BQ 3/4 Ford FB11003Q
- 3. Type K Copper
- 4. 30" x 60" opening single leaf aluminum door, pedestrian rated (300 lb/ft^2)
- 5. 4" Class 52 D.I.P.
- 6. 2" drain hole

Component Detail



Pipe detail for taps



Approved for Production

Project:	Date:

Quantity: By:

Specifications

Concrete: 5,000 psi minimum strength (28 day)

Pipe Penetrations: All pipe penetrations are placed according to job requirements.

3-Gang 3/4" Meter Vault **City of Clarksville**

P.O. Box 370 - Kingston TN 37763 Phone 888.882.5860 - BargerPrecast.com Date: 12.202024

Drawn By: Samantha Lowe

Approx. Empty Weight: 3,100 lbs.